

LONDON BOROUGH OF HOUNSLOW SMALL SITES SMALL BUILDERS PROGRAMME

BEACONSFIELD CLOSE, CHISWICK, W4 4EL

Archaeological Desktop Appraisal

10030793-ARC-XX-XX-RP-LH-0196-01

NOVEMBER 2019

Incorporating

EC HARRIS
BUILT ASSET
CONSULTANCY

Hyder

Beaconsfield Close, Chiswick, W4 4EL

Archaeological Desktop Appraisal

Author Alexandra Latham

Checker Kate Clover

Approver James Gidman

Report No 10030793-ARC-XX-XX-RP-LH-0196-01

Date NOVEMBER 2019

VERSION CONTROL

Version	Date	Author	Changes
01	Nov 2019	AL	First Issue

This report dated 21 November 2019 has been prepared for London Borough on Hounslow (the "Client") in accordance with the terms and conditions of appointment dated 25th October 2019 (the "Appointment") between the Client and **Arcadis Consulting (UK) Limited** ("Arcadis") for the purposes specified in the Appointment. For avoidance of doubt, no other person(s) may use or rely upon this report or its contents, and Arcadis accepts no responsibility for any such use or reliance thereon by any other third party.

CONTENTS

VERSION CONTROL 1

SUMMARY 1

1 INTRODUCTION 2

1.1 Background 2

1.2 Scope of Works 2

1.3 Limitations 2

2 SITE OVERVIEW 3

3 DATA SOURCES 4

4 BASELINE CONDITIONS 5

4.1 Designated Heritage Assets 5

4.2 Non-designated Heritage Assets 5

4.3 Historic Mapping Analysis 7

4.4 Previous Archaeological Events 7

5 KEY CONSTRAINTS AND RISKS 12

6 RECOMMENDATIONS 13

FIGURES 14

TABLES

Table 1: Designated Heritage Assets within the 500m study area 7

Table 2: Non-Designated Heritage Assets within the 500m study area 8

Table 3: Archaeological Events within 500m study area 10

FIGURES

Figure 1: Nationally Designated Heritage Assets 14

Figure 2: Locally Designated Heritage Assets 15

Figure 3: Non-designated Heritage Assets 16

Figure 4: Archaeological Events 17

No table of figures entries found.

Summary

An archaeological desk-top appraisal has been carried out on three parcels, 20A, 20B, 20C, of land at Beaconsfield Close, Chiswick, W4 4EL, in the London Borough of Hounslow (the Sites). This involved a rapid information-gathering and review of the known historic environment resource within the Site and a 500m study area using information from publicly held sources. A brief assessment of potential heritage/archaeological constraints and opportunities at the Site has been made.

There are no designated assets within the Sites and no World Heritage Sites, Scheduled Monuments or Registered Parks and Gardens within the study area. All three Sites are, however, bounded by Wellesley Road Conservation Area (**CA1**). There are a further four Conservation Areas (**CA2-5**) within the study area but none have a bearing on the Sites as they are too far away.

There are no Listed Buildings within the Sites and 18 within the study area. Only the setting of Nos. 3-9 Harvard Road (**LB17**) has the potential to be impacted by Site 20C. This is due to the close proximity of the assets to the Site.

There are no non-designated heritage assets recorded within the Sites and the Sites do not fall within or near to any Archaeological Priority Areas. There are however 16 non-designated heritage assets (**1-16**) recorded from within the study area dating from the Prehistoric to Modern periods. These indicate that the Sites have a potential for buried archaeological remains. There are no Locally Listed Buildings within the Sites. However, 15 locally Listed Buildings are within the study area. The setting of only one of the locally listed buildings has the potential to be impacted by potential development of the Sites. This is a wall along Harvard lane (**LLB3**) which is located within close proximity to Site 20C.

A historic map regression exercise was conducted to reveal any previous modern impacts to the Sites. The exercise revealed that only one site, 20A, has been subject to 19th and 20th century development.

Any future planning application will need to take into consideration the setting and character of the Conservation Area, the Listed Building and Locally Listed Building. It is recommended that early consultation be conducted with the LPA's Conservation Officer.

Due to the potential for buried archaeological remains to be present on the Site it is recommended that early consultation be carried out with the Greater London Archaeological Advisory Service (GLAAS), who advise the Local Planning Authority, in order to fully understand the archaeological requirements on the Sites.

1 Introduction

1.1 Background

Arcadis Consulting (UK) Limited (Arcadis) have been commissioned by the London Borough of Hounslow, 'the Client', to undertake an archaeological desk-top appraisal at three sites, 20A, 20B and 20C, on Beaconsfield Close, Chiswick (the Sites).

The London Borough of Hounslow authority is aiming to divest a number of small sites to enable regeneration. The objective of the Small Sites Small Builders Programme is to provide robust and pragmatic advice that sensibly de-risks each of the sites such that unreasonable 'abnormal' development costs are not incurred by developers.

The objective of this archaeological desktop appraisal is to identify potential constraints due to the presence of below ground archaeological remains and above ground heritage assets on or near to the Sites.

1.2 Scope of Works

The scope of the review is to carry out a desk-top search of publicly available information on designated and non-designated heritage assets within a study area of 500m of the Sites boundary. Using this information, a brief assessment of potential heritage/archaeological constraints and opportunities at the Sites has been made, focusing on key constraints. The appraisal also highlights when a site should be subject to further detailed assessment to support a planning application for any future development.

1.3 Limitations

This report has been prepared for The London Borough of Hounslow in accordance with the terms and conditions of appointment. Arcadis cannot accept any responsibility for any use of or reliance on the contents of this report by any third party. The copyright of this document, including the electronic format shall remain the property of Arcadis.

This report has been compiled from a number of sources, which Arcadis believes to be trustworthy. However, Arcadis is unable to guarantee the accuracy of information provided by others. The report is based on information available at the time. Consequently, there is a potential for further information to become available, which may change this report's conclusion and for which Arcadis cannot be responsible.

2 Site Overview

The three Sites, 20A, 20B, 20C, are located at TQ201780. The Sites are located within a complex of five blocks of flats off Beaconsfield Close. Site 20A, measures 0.0148ha, is nearly square in shape with a row of garages to the west and an area of concrete to the east. Site 20B, measuring 0.0064ha, is trapezium in shape and comprises of four garages with a storage area to the south west. Site 20C, measuring 0.0607ha, comprises of a near triangular plot of land with two rows of garages and an area of concrete used for parking.

The Sites are surrounded by the flat complex and its landscaping. Within the wider area is a residential neighbourhood with the busy A4 Cedars Road to the south. All three sites lie at c.11m AOD.

The Sites are located on the London Clay Formation – clay, silt and sand with the sedimentary bedrock being formed approximately 48 – 56 million years ago in the Palaeogene Period (British Geological Survey Online Map Viewer, access November 2019). The superficial geology is made up of the Kempton Park Gravel Member- a sand and gravel combination formed approximately 2 million years ago in the Quaternary Period.

3 Data Sources

Information on designated and non-designated heritage assets that are located within 500m of the Sites were assessed. Designated data was derived from the National Heritage List for England on 11 November 2019. Non-designated data was received from the Greater London Historic Environment Record (GLHER) on the 11 November 2019. Information on Conservation Areas was obtained from the London Borough of Hounslow Council website on 12 November 2019

(https://www.hounslow.gov.uk/info/20010/planning_and_building/1868/conservation_area_appraisals_and_maps).

Information regarding Locally listed Buildings was found on the London Borough of Hounslow Council website on 12 November 2019

(https://www.hounslow.gov.uk/info/20010/planning_and_building/1098/design_and_conservation/6).

Numbers in brackets in the text are unique identifiers (Project ID. numbers) assigned to heritage assets for the purposes of this report. A list of all heritage assets including relevant archaeological events can be found in Tables 1, 2 and 3. All national designated heritage assets i.e. Listed Buildings and Conservation Areas can be found on Figure 1. All locally designated heritage assets i.e. Archaeological Priority Areas (APAs) and Locally Listed Buildings can be found on Figure 2. All non-designated heritage assets i.e. findspots, archaeological remains and extant buildings are shown on Figure 3. All archaeological events are shown on Figure 4.

4 Baseline Conditions

4.1 Designated Heritage Assets

There are no World Heritage Sites, Scheduled Monuments, Registered Parks and Gardens or assets on the heritage at risk register, located within the Sites or within the 500m study area.

Listed Buildings

There are no Listed Buildings located within the Sites, and 18 (**LB1-18**), all Grade II, located within the 500m study area. The closest to the Sites are No. 3-9 Harvard Road (**LB17**) located c.30m south-west of Site 20B and c.40m to the north of Site 20C. The rear of the Listed properties borders the north-western side of the flat complex in which all three Sites are located.

Conservation Areas

There are five Conservation Areas (**CA1-5**) within the study area, one, Wellesley Road (**CA1**), borders all three Sites. This Conservation Area is based on the 19th century developments of Adam Askew, Alfred Kendall and William Tomlinson. Askew developed large areas of land for suburban housing within Chiswick. The Conservation Area is also based on the ancient route of Wellesley Road which developed into a route from the market gardens of West Middlesex to Covent Garden. This road is believed to be Roman or older in origin. The Conservation Area's special architectural and historic interest lies in its high quality and wide-ranging Victorian architecture.

The other Conservation areas are; Turnham Green (**CA2**), thorny Hedge (**CA3**), Chiswick House (**CA4**) and Strand on the Green (**CA5**). All of these are far enough away from the Sites not to be affected by the proposed developments.

4.2 Non-designated Heritage Assets

Archaeological Priority Areas

There is one Archaeological Priority Area within the 500m study area. The boundary of the APA, known as Staines Road/London Road (**APA1**), lies c.330m to the north of the Sites. The APA has been allocated due to the tentative line of a Roman road that ran from Londinium to Silchester and to the west. It is not clear if the road existed here and no non-designated assets connected with such road have been recorded by the HER. Only one Roman non-designated asset has been recorded by the HER, a coin hoard in an urn (**9**). The lack of Roman artefacts and archaeological remains could be the result of the lack of opportunity to record and recover such assets as opposed to lack of remains.

Whilst APAs do not receive statutory protection they have a high potential for below-ground archaeological remains to survive. Historic England's website provides more information about APAs and the different levels of sensitivity to development (<https://www.historicengland.org.uk/services-skills/our-planning-services/greater-london-archaeology-advisory-service/greater-london-archaeological-priority-areas/>).

Locally Listed Buildings

There are no Locally Listed Buildings within the Sites and 15 located (**LLB1-15**) within the 500m study area. The two closest to the Sites are No.1 Harvard Road (**LLB5**) c.30m to the north-west of 20B and a brick wall along Harvard lane (**LLB3**), c.30m to the south-west of 20C. It is not clear if the brick wall extends the whole length of Harvard Lane, if it does then any development within 20C will have to consider the setting of this locally listed wall.

While Locally Listed Buildings do not receive statutory protection, they have been identified in the Borough's Local Plan of being of historic or architectural interest (https://www.hounslow.gov.uk/info/20010/planning_and_building/1098/design_and_conservation/6).

Non-Designated Heritage Assets

There are no non-designated heritage assets within the Sites and 16 (**1-16**) within the 500m study area. These date from the Prehistoric to the Modern period.

There are five assets (**1,3,4,5,8**) which date to the Prehistoric period. The first is an assemblage of Palaeolithic animal fossils (**1**) which were found c.480m to the north-east of the Sites. These fossils were found on a gravel terrace during excavations during the early 1870's. The second was a flint implement (**3**) found c.390m to the north-east of the Sites. The HER does not specify what type of flint implement it is nor its context i.e. during an excavation etc.

To the north-west, c.480m of the Sites, three assets (**4, 5, 8**) were found during an evaluation (**EV5**) at the former London Road bus works in 1989. The first artefact was a Neolithic transverse type arrowhead (**4**), the second was the remains of a settlement (**5**) and the third was a series of Prehistoric pits (**8**). The settlement (**5**) comprised of pits, postholes and ditches. These formed the northern edge of a small Late Bronze Age domestic occupation area. The HER did not specify if the pits (**8**) and the settlement (**5**) are connected.

There is only one non-designated heritage asset which dates to the Roman period found within the study area. An urn full of silver Roman coins (**9**) was discovered c.350m to the north-east of the Sites. This coin hoard is an important and uncommon find. This find was located c.240m to the south-west of the boundary of the Roman road APA (**APA1**). Wellesley Road, c.140m to the north of the Sites, is also believed to be Roman in origin. All of these remains add to our knowledge of the Roman presence within the study area.

There are two heritage assets of Medieval date (**6,10**) recorded within the 500m study area. The first was several pottery fragments (**6**) found within the same area as the prehistoric finds (**4,5,8**) at the former London Road bus works. The HER did not specify their find context nor type. The second is a non-extant manor house (**10**) located c.420m to the south-east of the Sites. This house was known as Sutton Manor in 1181 and later as Sutton Court in 1537. By 1589 the house boasted a gatehouse, malt house, dovecote and farm buildings, all of which suggest that its occupants were wealthy. It is not known when the asset became non-extant. The area is now occupied by flats.

Only one asset dates to the Medieval to Post Medieval period. Little Sutton (**11**) was a settlement located c.215m to the north of the Sites. The asset was first recorded in 1181, it was later known as Sutton Beauregard in the 1540's. In 1706 it was known to have contained '*only a few poor cottages*'. The settlement site is now occupied by residential housing and roads. The Conservation Area, Wellesley Road (**CA1**), borders the Sites and is noted for its Medieval to Post Medieval route way. The exact location of this road is not known but its presence, and that of Little Sutton (**11**), indicates at a strong Medieval to Post Medieval presence within the study area.

Two assets (**13,16**) date to the Medieval to Modern periods. The first is Sutton Court Road Park (**13**) located c.340m to the south-east. This park is the remains of the grounds of the manor house (**10**). Originally the park contained a formal planted area, tennis courts and croquet lawn. These have since been replaced with an extant ornamental garden. The second asset is a Chiswick High Road Park (**16**) located c.275m to the north-east of the Sites. This triangular plot of land, also known as Turnham Green, is bisected by a north to south road. It was originally built to serve the inhabitants of the Victorian villas located along Chiswick High Road. It now is a public open space with flower beds, trees, grass and a war memorial.

There are two assets (**7, 14**) which date to the Post Medieval period. The first is a settlement site (**7**) found where the Prehistoric and Medieval assets were at the former London Road bus works. This settlement comprised of a small cluster of pits and ditches dating to the 17th to 19th centuries. The HER did not provide any more information on the asset. The second is the site of a Civil War battle (**14**), located c.75m to the east of the Sites. The event was known as the Battle of Turnham Green which took place on the 13th of November 1642. The Royalist Army was marching towards London where their way was blocked by an Essex Parliamentary regiment. The Royalists were aligned on Turnham Green and Acton Green. The Parliamentarians were positioned along Acton Green and Chiswick Common Fields. The battle comprised of a few skirmishes and artillery fire. The Royalist retreated and wintered in Oxford.

Only one asset dates to the Post Medieval to Modern period. No. 64 and 66 Grove Park Terrace (**15**) is located c.465m to the south of the Sites. The extant buildings were constructed in the 19th century out of brown brick over two storeys. These properties were once Listed but have been de-Listed for unknown reasons.

There are two assets within the study area which date to the Modern period (**2,12**). The first was a pit (**2**) found during an evaluation (**EV1**). The pit contained early 20th century pottery, glass bottles and general

waste. The asset was located c.375m to the north north-east of the Sites. The second is the extant Church of St Michaels (**12**) which it is located c.300m to the east of the Sites. It was constructed in 1909 out of red brick in a late Gothic style with vernacular influence. The building was once Listed but it has since been de-Listed for unknown reasons.

4.3 Historic Mapping Analysis

Historic OS mapping for the Site was acquired from Groundsure and a short map regression exercise has been carried out. The earliest map, 1867, shows that the Site was located within a wooded area. By 1896 the woodland has gone and been replaced with a residential neighbourhood. The properties along Harvard Road have been established which creates the north-western sides of Sites 20C and 20B. Site 20A is shown as being part of a small green area as is Site 20C. It is not clear what the usage of Site 20B was at this time.

By 1915 a small square structure had been built in Site 20A. On a map from 1950 this is labelled as a pavilion. Site 20C is shown on this map as allotments. Between 1961-65 the garages and concrete areas were established as well as the flat complex. All three Sites remained unaltered until the present day.

During the Blitz in WWII a high explosive bomb was dropped close to the Sites, on Cedar Road. It is not clear if this event caused any impact to the Sites or any belowground archaeological remains (<http://bombsight.org/#>).

4.4 Previous Archaeological Events

No archaeological investigations have taken place within the Sites. However, five intrusive archaeological events/investigations have occurred within the 500m study area. The first was a trial trenching event (**EV1**) located at Nos. 331-335 Chiswick High Road, c.385m to the north of the Sites. A single trench was excavated and revealed a 20th century pit (**12**).

The next two events comprised of an evaluation (**EV3**) and a watching brief (**EV2**) at Gunnersbury Mews c.390m to the north-west of the Sites. The evaluation (**EV3**) found a 17th century ditch, Post Medieval agricultural soil and 18th to 19th century agricultural soils. The subsequent watching brief (**EV2**) revealed that the 17th century ditch was a Post Medieval quarry.

The fourth event was an evaluation (**EV4**) located c.480m to the north-west of the Sites. No archaeological features, deposits or artefacts were recorded.

The last event was also an evaluation (**EV5**), c.400m to the north-west of the Sites, which revealed the Prehistoric, Medieval and Post Medieval artefacts and archaeological remains (**4,5,6,7,8**) at the former London Road bus works.

Table 1: Designated Heritage Assets within the 500m study area.

Project ID	Asset Name	Designation Grade	NHLE/GLHER Entry Number	Easting	Northing
Listed Buildings					
LB1	58, GROVE PARK TERRACE W4	II	1080328	519949	177559
LB2	68 AND 70, GROVE PARK TERRACE W4	II	1080329	519989	177604
LB3	10 AND 11, HEATHFIELD TERRACE W4	II	1080337	520556	178358
LB4	16-19, HEATHFIELD TERRACE W4	II	1080338	520462	178335
LB5	22-26, HEATHFIELD TERRACE W4	II	1080339	520436	178329
LB6	80-94, GROVE PARK TERRACE	II	1096979	520036	177659

Project ID	Asset Name	Designation Grade	NHLE/GLHER Entry Number	Easting	Northing
LB7	RAILINGS TO GARDEN OF NUMBER 24	II	1189662	520421	178342
LB8	ARLINGTON COTTAGES	II	1240569	520318	178454
LB9	CHURCH OF ST MICHAEL	II	1240805	520091	177900
LB10	CHISWICK TOWN HALL (FORMER)	II	1260615	520518	178335
LB11	BOUNDARY WALL TO EAST SIDE AND REAR OF LITTLE SUTTON COTTAGE AND TO REAR AND WEST OF SUTTON CLOSE	II	1260819	520147	177951
LB12	21, HEATHFIELD TERRACE W4	II	1294155	520450	178332
LB13	12 AND 13, HEATHFIELD TERRACE W4	II	1294191	520544	178355
LB14	LITTLE SUTTON COTTAGE	II	1294387	520169	177969
LB15	GARDEN WALL AND GATEPOSTS	II	1358311	519959	177571
LB16	20, HEATHFIELD TERRACE W4	II	1358319	520456	178333
LB17	3-9, HARVARD ROAD	II	1390999	520063	178111
LB18	FORMER VICARAGE TO THE CHURCH OF ST MICHAEL SUTTON COURT	II	1391464	520093	177952

Conservation Areas

CA1	Wellesley Road	-	-	519822	178188
CA2	Turnham Green	-	-	520464	178386
CA3	Thorney Hedge	-	-	519684	178573
CA4	Chiswick House	-	-	520772	177516
CA5	Strand on the Green	-	-	519467	177743

Table 2: Non-Designated Heritage Assets within the 500m study area

Project ID	Asset Name	Site Type	Period	GLHER Number	Easting	Northing
Locally Listed Buildings						
LLB1	The Gunnersbury Public House	Locally Listed Buildings	Modern	-	519795	178474

Project ID	Asset Name	Site Type	Period	GLHER Number	Easting	Northing
LLB2	Queens Head Public House	Locally Listed Buildings	Modern	-	520198	178080
LLB3	Brick Wall Along Harvard Lane	Locally Listed Buildings	Modern	-	519996	178038
LLB4	Churchdale Court	Locally Listed Buildings	Modern	-	519836	178118
LLB5	No.1 Harvard Road	Locally Listed Buildings	Modern	-	520077	178150
LLB6	No. 30 Grange Road	Locally Listed Buildings	Modern	-	519902	178370
LLB7	Arlington Park House	Locally Listed Buildings	Modern	-	520355	178420
LLB8	HSBC	Locally Listed Buildings	Modern	-	520401	178494
LLB9	Former First Church of Christ	Locally Listed Buildings	Modern	-	520089	178443
LLB10	The Pilot Public House	Locally Listed Buildings	Modern	-	519667	178221
LLB11	Cathedral of the Nativity	Locally Listed Buildings	Modern	-	519788	178162
LLB12	Former Gunnersbury Baptist Church	Locally Listed Buildings	Modern	-	520203	178111
LLB13	Gunnersbury Baptist Church and Manse	Locally Listed Buildings	Modern	-	520029	178239
LLB14	Arlington Park Mansions	Locally Listed Buildings	Modern	-	520372	178445
LLB15	No. 2-20 Grange Road	Locally Listed Buildings	Modern	-	519943	178356

Archaeological Priority Areas

APA1	Staines Road / London Road	APA	Roman	DLO35691	514511	176064
------	----------------------------	-----	-------	----------	--------	--------

HER Assets

1	Chiswick Road	Findspot	Palaeolithic	MLO103065	520305	178573
2	Nos 331-335 Chiswick High Road	Monument	Modern	MLO104879	520236	178486

Project ID	Asset Name	Site Type	Period	GLHER Number	Easting	Northing
3	Turnham Green	Findspot	Palaeolithic	MLO1960	520405	178405
4	Former London Road Transport Bus Works	Findspot	Neolithic	MLO22185	519800	178500
5	Former London Road Transport Bus Works	Monument	Late Bronze Age	MLO22186	519800	178500
6	Former London Road Transport Bus Works	Findspot	Medieval	MLO22187	519800	178500
7	Former London Road Transport Bus Works	Monument	Post Medieval	MLO22188	519800	178500
8	Former London Road Transport Bus Works	Monument	Prehistoric	MLO22189	519800	178500
9	Turnham Green	Findspot	Roman	MLO249	520405	178305
10	Fauconberg Road	Monument	Medieval	MLO68838	520305	177705
11	Settlement of Little Sutton	Settlement	Medieval to Post Medieval	MLO68842	520155	178340
12	Church of St Michael	Findspot	Modern	MLO85606	520433	178069
13	Sutton Court Road Park	Park	Medieval to Modern	MLO104560	520301	177752
14	Battle of Turnham Green	Battle	Post Medieval	MLO105154	520791	178254
15	Nos 64 and 66 Grove Park Terrace	Building	Post Medieval to Modern	MLO85423	519971	177585
16	Chiswick High Road Park	Park	Medieval to Modern	MLO104544	520426	178410

Table 3: Archaeological Events within 500m study area

Project ID	Event Name	Event Date	Event Type	GLHER Number	Easting	Northing
EV1	Nos 331-335 Chiswick High Road	2011	Evaluation	ELO11880	520237	178492
EV2	Gunnersbury Mews	2013	Watching Brief	ELO13146	519794	178405
EV3	Gunnersbury Mews	2013	Evaluation	ELO13148	519783	178369
EV4	No 590 Chiswick High Road	2008	Evaluation	ELO8041	519788	178512

Project ID	Event Name	Event Date	Event Type	GLHER Number	Easting	Northing
EV5	Former London Road Transport Bus Works	1989	Evaluation	ELO3938	519887	178612

5 Key Constraints and Risks

In summary, all three Sites are bounded by Wellesley Road Conservation Area (**CA1**) who's setting may be affected by the redevelopment of the Sites. Site 20B may affect the setting of the Listed Buildings at Nos. 3-9 Harvard Road (**LB17**). Site 20C may affect the setting of the Locally Listed Building, wall along Harvard Lane (**LLB3**), as it is within close proximity. Any future re-development of the Sites would have to consider its effect on the character of these assets. All other designated assets (**CA2-5, LB1-16, LB18**), Archaeological Priority Areas (**APA1**) and Locally Listed Buildings (**LLB1-2, LLB4-15**) are far enough away not to be affected.

There are no recorded non-designated heritage assets within the Sites. The study area contains 16 non-designated heritage assets which date to the Prehistoric to Modern periods. None are in close proximity to the Sites. However, this lack of recorded archaeological does not necessarily mean the lack of archaeological potential merely the lack of opportunity to discover and record archaeological remains and artefacts. There is still a potential for buried archaeological remains to be within the Sites from all time periods, particularly from the Roman and Medieval to Post Medieval periods due to close proximity of the ancient route way of Wellesley Road and the Conservation Area.

There are no previous archaeological events recorded within any of the three Sites. None of the finds resulting from these investigations have a bearing on the Sites' archaeological potential due to distance from the Sites.

The historic map regression exercise revealed that only one Site, 20A, has had a previous intrusive impact. Site 20C once contained allotments and Site 20B has had no reported structures build on it until the current garages were built. This could mean that Sites 20B and C have a high potential for buried archaeological remain to survive.


6 Recommendations

Any future planning application will need to take into consideration the setting and character of the Wellesley Road Conservation Area, and the nearest Listed Building and Locally Listed Building. It is recommended that early consultation be conducted with the local conservation and planning officers. The officers may recommend further assessment such as a heritage statement.

For any future planning application, the potential for below ground archaeological remains need to be considered. The Greater London Archaeological Advisory Service (GLAAS) who advise the local planning authority might recommend a full archaeological desk-based assessment (DBA) for the Site. The DBA would include a specific archaeology site walkover, relevant documentary research, a map regression exercise as well as preparation of distribution maps showing designated and undesignated heritage assets. Intrusive archaeological investigations, if determined to be required, would likely consist of a programme of trial trenching and subsequent reporting. This investigation may be added as a planning condition for any development on the Site or could be required prior to a planning decision. Early consultation with GLAAS is highly recommended to understand the requirements. Should archaeological remains of significance be located, additional mitigation would be required prior to construction commencing.

FIGURES





Figure 1: Nationally Designated Heritage Assets



Contains OS data © Crown Copyright and database right 2019

01	19 Nov 19	INITIAL ISSUE	YG	JN	JG
REV	Date	Description	Drawn	Check	Approv

Legend

-  Red Line Boundary
-  500m Buffer Study Area
-  Listed Building
-  Conservation Areas

Client



Site

Garages on the South West Side of North Street and the North Side of Hartland Road Isleworth, TW7 6RH London

London Borough of Hounslow

Hounslow House


7 Bath Road

Hounslow

TW5 3EB

Suitability Description:			
Issued for information			
Designed	A. Latham	Date 19 Nov 19	Signed
Drawn	Y. Giri	Date 19 Nov 19	Signed
Checked	J. Norman	Date 19 Nov 19	Signed
Approved	J. Gidman	Date 19 Nov 19	Signed
Scale:	1:5,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	S2	Project Number:	10030793

	PROJECT:	
	Hounslow Small Sites	
	TITLE:	
	Figure 1:	
	Nationally Designated Heritage Assets	
	Site 20 - Beaconsfield Close, Chiswick	



ARCADIS

Design & Consultancy
for natural and
built assets

Registered office:
Arcadis House
34 York Way,
London
N1 9AB

Coordinating office:
Level 1
2 Glass Wharf
Temple Quay
Bristol
BS2 0FR

www.arcadis.com



Drawing Number:

10030793-ARC-XX-XX-DR-LH-0197-01

Revision:

01

Figure 2: Locally Designated Heritage Assets



Contains OS data © Crown Copyright and database right 2019

REV	Date	Description	Drawn	Check	Approv
01	19 Nov 19	INITIAL ISSUE	YG	JN	JG

Legend					
	Red Line Boundary				
	500m Buffer Study Area				
	Locally Listed Building				
	Locally Listed Building				
	Archaeological Priority Areas				

Client



London Borough of Hounslow

Client

London Borough of Hounslow
Hounslow House
7 Bath Road
Hounslow
TW3 3EB

Site

Garages on the South West Side of
North Street and the North Side of
Harland Road
Isleworth, TW7 6RH
London


Suitability Description:			
Issued for information			
Designed	A. Latham	Date 19 Nov 19	Signed
Drawn	Y. Giri	Date 19 Nov 19	Signed
Checked	J. Norman	Date 19 Nov 19	Signed
Approved	J. Gidman	Date 19 Nov 19	Signed
Scale:	1:5,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	S2	Project Number:	10030793

PROJECT:

Hounslow Small Sites

TITLE:

Figure 2:
Locally Designated Heritage Assets,
Site 20 - Beaconsfield Close, Chiswick



ARCADIS

Design & Consultancy
for natural and
built assets

Registered office:
Arcadis House
34 York Way,
London
N1 9AB

Coordinating office:
Level 1
2 Glass Wharf
Temple Quay
Bristol
BS2 0FR

www.arcadis.com



Drawing Number:

10030793-ARC-XX-XX-DR-LH-0198-01

Revision:

01

Figure 3: Non-designated Heritage Assets



Contains OS data © Crown Copyright and database right 2019

01	19 Nov 19	INITIAL ISSUE	YG	JN	JG
REV	Date	Description	Drawn	Check	Approv

Legend

- Red Line Boundary
- 500m Buffer Study Area
- Non-Designated Heritage Assets
- Points
- Polygons

Client

London Borough of Hounslow

Client

London Borough of Hounslow
Hounslow House
7 Bath Road
Hounslow
TW3 3EB

Site

Garages on the South West Side of North Street and the North Side of Hartland Road
Isleworth, TW7 6RH
London

Client

London Borough of Hounslow

Client

London Borough of Hounslow
Hounslow House
7 Bath Road
Hounslow
TW3 3EB

Site

Garages on the South West Side of North Street and the North Side of Hartland Road
Isleworth, TW7 6RH
London

Suitability Description:			
Issued for information			
Designed	A. Latham	Date	19 Nov 19
Drawn	Y. Giri	Date	19 Nov 19
Checked	J. Norman	Date	19 Nov 19
Approved	J. Gidman	Date	19 Nov 19
Scale:	1:5,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	S2	Project Number:	10030793

PROJECT:

Hounslow Small Sites

TITLE:

Figure 3:
Non-Designated Heritage Assets,
Site 20 - Beaconsfield Close, Chiswick

ARCADIS

Design & Consultancy
for natural and
built assets

Registered office: Arcadis House
34 York Way,
London
N1 9AB

Coordinating office: Level 1
2 Glass Wharf
Temple Quay
Bristol
BS2 0FR

www.arcadis.com


Drawing Number:

10030793-ARC-XX-XX-DR-LH-0199-01

Revision:

01

Figure 4: Archaeological Events



Contains OS data © Crown Copyright and database right 2019

REV	Date	Description	Drawn	Check	Approv
01	14 Nov 19	INITIAL ISSUE	YG	JN	JG

Legend					
	Red Line Boundary				
	500m Buffer Study Area				
	Archaeological Priority Areas				

Client

London Borough of Hounslow
Client
London Borough of Hounslow
Hounslow House
7 Bath Road
Hounslow
TW3 3EB

Site
Garages on the South West Side of
North Street and the North Side of
Hartland Road
Isleworth, TW7 6RH
London

Suitability Description:			
Issued for information			
Designed	A. Latham	Date 14 Nov 19	Signed
Drawn	Y. Giri	Date 14 Nov 19	Signed
Checked	J. Norman	Date 14 Nov 19	Signed
Approved	J. Gidman	Date 14 Nov 19	Signed
Scale:	1:5,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	S2	Project Number:	10030793

PROJECT:
Hounslow Small Sites

TITLE:
Figure 4:
Archaeological Events,
Site 20 - Beaconsfield Close, Chiswick

ARCADIS
Design & Consultancy
for natural and
built assets

Registered office: Arcadis House
34 York Way,
London
N1 9AB
www.arcadis.com

Coordinating office:
Level 1
2 Glass Wharf
Temple Quay
Bristol
BS2 0FR

Drawing Number:
10030793-ARC-XX-XX-DR-LH-0200-01

Revision:
01

Arcadis Consulting (UK) Limited

Level 1

2 Glass Wharf

Temple Quay

Bristol

BS2 OFR

[arcadis.com](https://www.arcadis.com)

A decorative graphic consisting of three thin orange lines. One line is horizontal, extending across the width of the page. Two other lines are diagonal, starting from the bottom left and extending towards the top right, intersecting the horizontal line.